




Buffalo Niagara Waterkeeper

# Crescent Beach Living Shoreline Conceptual Design

February 2020



# Crescent Beach Resiliency & Economic Development Initiative (REDI) Project



The primary objective of the Crescent Beach Resiliency and Economic Development Initiative (REDI) Project is to design and construct a natural or nature-based shoreline system that will protect Crescent Beach from Lake Ontario wave action and enhance the overall resiliency of the barrier beach.


## Step 1:

### Preliminary Engineering Report

to analyze the coastal setting & provide conceptual design alternatives


# Shoreline Stabilization Challenges & Techniques

- Record high water levels
- Continuous wave action
- Flooding, over wash, erosion
- Damage & loss of property, mature trees, vegetation
- Displacement of material & barrier bar breach



NOAA Shoreline Stabilization Techniques (2015)

# NOAA Water Levels





Notes: IGLD85 = International Great Lakes Datum of 1985, WSEL = Water Surface Elevation, LWD = Low Water Datum

- Measured Hourly WSEL at Rochester, NY (NOAA 9052058 1961 to 2016)
- Measured Hourly WSEL at Oswego, NY (NOAA 9052030 1965 to 2016)
- Measured Hourly WSEL at Rochester, NY (NOAA 9052058 2017 to 2019)
- Measured Hourly WSEL at Oswego, NY (NOAA 9052030 2017 to 2019)
- - - Lake Ontario LWD

# USACE Water Level Forecast

## LAKE ONTARIO WATER LEVELS - JANUARY 2020




\*\* Average, Maximum and Minimum for period 1918-2018

# USACE Wind & Waves



Lake Ontario WIS Station 91058  
 ANNUAL 2014  
 Long: -76.98° Lat: 43.3° Depth: 21 m  
 Total Obs / Total Ice : 8759 / 840

## WAVE ROSE




SIG WAVE HEIGHT (m)




Lake Ontario WIS Station 91058  
 ANNUAL 2014  
 Long: -76.98° Lat: 43.3° Depth: 21 m  
 Total Obs : 8759


## WIND ROSE



WIND SPEED (m/s)



# Ice





# Conceptual Design Plan View


Note: Barrier rock reef alignment is between the -2' and -3' contour below LWD based on the NOAA Navigation Chart, which places the crest around the USACE OHWM elevation.



## DATA


LWD: 243.3'  
OHWM: 247.3'  
Min reef length: 150'  
Max reef length: 400'  
Min distance offshore: 200'  
Max distance offshore: 350'  
Overall project length: 7,200'  
Total reef length: 3,650'

# Conceptual Design Sections



## Fish Piles & Barrier Rock Reef

NOT TO SCALE



## Root Wad & Barrier Rock Reef

NOT TO SCALE

# Anticipated Community Benefits



*The barrier bar reef will directly improve the coastal resilience of Crescent Beach, but also provide the following benefits to the surrounding community:*



Conserve & enhance local ecosystems



Retain walkability & water access for residents



Support for local tourism & recreational economy




Improve both water-based & land-based recreation



Provide visual quality & diversity in selection of materials, appearance, & placement

# Timeline

## PROJECT SCHEDULE BY MONTH



### INFORMATIONAL MEETINGS:

- PSC (★) Project committee meetings to discuss upcoming meetings, items, & project progress
- PIM ① Public workshop to display PER data collection, preliminary design, & visual preference
- PIM ② Open house to present final design
- PIM ③ Attendance at local event to update on construction progress

### PROJECT OUTREACH:

Outreach will include monthly updates via social media and regular upload of materials to project website. Areas highlighted in dark blue indicate peak periods when material & updates are distributed more frequently.

### POST-CONSTRUCTION

Performance monitoring & construction for living system may continue beyond 3-years.

# Next Steps

- Permit Pre-Application meeting with NYSDEC, NYSDOC, USACE
- Begin Design Activities
  - Field data collection, including bathymetry survey
  - Hydrodynamic wave model development
- Public Outreach
  - Schedule first meeting at the beginning of summer 2020
  - Use existing social media platforms to provide continuous stream of materials and solicit an on-going dialogue